

## INSTALLATION RATE CARD

### Standard Installation

The following items/services are included as part of your installation.

ITEMS / SERVICES	QTY
<u>Landed Homes (SDU) with Non Pre-laid Fibre</u> Fibre optic cabling from Fibre Termination Box (FTB) to Optical Network Unit (ONU) *FTB should be placed next to Point of Entry (POE)	40 metres
<u>High-rise Buildings (MDU) with Non Pre-laid Fibre</u> Fibre optic cabling from POE to ONU with surface casing enclosure	20 metres
<u>Landed Homes/High-rise Buildings (SDU/MDU) with Pre-laid Fibre</u> Fibre optic cabling from socket	6 metres
<u>High-rise Buildings (MDU) with Pre-laid Fibre for 2Gbps/Small or Home Offices (SOHO) with Patch Panel</u> Fibre optic cabling from socket to ONU	20 metres
Cat-5E cabling from ONU to WiFi router	1 metres
Installation and configuration of devices for broadband and voice services • ONU • WiFi router • Phone (if applicable) • WiFi Mesh AP (if applicable)	1 unit
Drilling of the initial hole up to POE (Point of Entry) is included if required.	1 unit
<b>STANDARD INSTALLATION FOR FIBRE-TO-THE-ROOM (FTTR)</b>	
<u>1 parent node + 1 child node package</u> Supply and installation of transparent fibre cable from parent node (ONU) to child node(s) Child node(s) Indoor Access Terminal Box (ATB) Fibre Distribution Unit (FDU) Field Mountable Connector (FMC)	50 metres 1 unit 1 unit 1 unit 4 units
<u>1 parent node + 2 child nodes package</u> Supply and installation of transparent fibre cable from parent node (ONU) to child node(s) Child node(s) Indoor Access Terminal Box (ATB) Fibre Distribution Unit (FDU) Field Mountable Connector (FMC)	75 metres 2 units 2 units 1 unit 6 units
<u>1 parent node + 3 child nodes package</u> Supply and installation of transparent fibre from parent node (ONU) to child node(s) Child node(s) Indoor Access Terminal Box (ATB) Fibre Distribution Unit (FDU) Field Mountable Connector (FMC)	100 metres 2 units 2 units 1 unit 6 units

### Non-Standard Installation

The following items/services are not included as part of your installation and are chargeable as follows.

The following items/services will be billed by Time post-installation.

ITEMS / SERVICES	UNIT	RATE (RM)/UNIT
Fibre patch cord	Unit	15.00
Fibre connector	Unit	30.00

The following items/services are to be paid directly to the attending Service Installer by cash or QR Pay.

ITEMS / SERVICES	UNIT	RATE (RM)/UNIT
<u>High-rise Buildings (MDU)</u> Supply and installation of new fibre optic cable from riser room to Point of Entry (upon customer's request)	Unit	300.00
Supply and installation of additional fibre optic cable (applicable for distance beyond standard installation length)	Metre	10.00
Supply and installation of additional Cat-5E cable	Unit	10.00
Installation of access port within customer premises: To cut open, access, repatch and repaint the port (white, matex paint) (applicable within customer's house)	Unit	50.00
Additional drilling with repatch and repaint (white, matex paint) (applicable for drilling beyond standard installation within customer's house)	Unit	50.00
WiFi configuration, troubleshooting and other IT support services for customer's own devices (desktops, laptops or other devices that are not supplied by Time)	Hour	80.00 <i>Max. RM300 per day</i>
Supply and installation of shelving for device	Unit	100.00
Installation of fibre cable laid through the roof to the ceiling with protection (PVC piping or micro duct)	Unit	100.00
Supply and installation of additional cable protection (PVC or micro duct) for more than 5 metres	Metre	5.00
<b>NON-STANDARD INSTALLATION FOR FTTR</b>		
Supply and installation of additional transparent fibre cable (applicable for distance beyond complimentary length)	Metre	10.00